




Important Factors for FY10 Startup Planning

**H. W. Kugel
Nov. 20, 2009**

LLD-1 Installation Proceeding on Schedule for FY10 Operation



4 LLD Plates Installed



**Control Rack
Installed**



**99 Probe
LP Array**


LLD-1 FY10 Test Plans

- **Testing LLD-1 in air (room temp+10° for seconds) starts 11/23/09.**
- **LLD-1 will be tested in vacuum prior to Bake (350°C).**
- **Vessel Bake for 3 weeks is proposed (to minimize effect of no TMB).**
- **LLD-1 will be tested during Bakeout (360°C to avoid condensation).**
- **LLD-1 will be tested after Bake cooldown at initial op temp (205°C).**
- **LLD-1 will be tested during plasma ISTP at initial operation temp. (205°C).**


Run Plan Should Avoid Damaging LLD-1 Porosity and Wetting Capability with TMB (BC_3^+) and Inert Depositions

- Key properties for an acceptable LLD-1 lithium surface
 - sufficient **surface tension** to hold Li in presence of JxB forces
 - ability of liquid Li to flow across metal surface (**wetting capability**)
 - minimize temperature rate of rise of Li \rightarrow rapid heat transfer to base
- Thin plasma sprayed porous Mo, on a thin SS-316 Li barrier, on thick Cu baseplate thermal sink is highest confidence initial approach

Cross sectional photos of plasma sprayed porous molybdenum LLD sample



Longitudinal





Transverse

- 37 gm lithium deposition required to fill available LLD-1 porous volume

LLD-1 LITER Loading Has 7% Efficiency


- LLD-1 Li fill capacity is **37 g**
- LITER deposition amount to fill LLD-1 is **530 g**



- The ability liquid Li to wet the porous Mo surface will spread the asymmetric LITER deposition.



- Simulation Finds 50% of Li Sputtered from LLD Redepleted on Outer Divertor
- Ion Beam Analysis of NSTX 2009 Tiles Finds Li Redeposition on Outer Divertor

- 50.3% of sputtered (neutral) lithium is ionized within the computation zone (LLD and associated near-surface grid). 49.7% of sputtered lithium “escapes”.



Gross and Net Erosion Rate Along LLD

- J.N. Brooks, J.P. Allain, Purdue Univ, PFC Meeting 7/09



IBA of NSTX 2009 Tiles



- W. R. Wampler, SNL, 11/09

11/20/09

Scenario Using Between Shot Evaporations to Load LLD-1

- Evaporate for 10 mins Between Shots until LLD-1 Full



- Fast Fill Rate for Fully Loaded LLD Li Physics
 - 22 days to load @80mg/min (4.4 run wks, 530g)
- Intermediate Fill Rate
 - 44 days to load @40mg/min (8.8 run wks, 530g)
- Normal Fill Rate (Maintain Contact with 2008-2009 Li Database)
 - 88 days to load @20mg/min (17.6 run wks, 530g)



Key Issues: • Achieve First Plasmas Without Boronization • Minimize Duration to LLD Commissioning

- The probability of achieving successful LLD-1 results and the Milestone is maximized by minimizing the duration between first plasma and the start of lithium deposition (Commissioning)
 - No boronization *to hinder wetting*
 - Minimal GDC and Discharge sputtering *to hinder wetting*
 - Minimal thermal and MHD stresses *to hinder mechanical damage*
- Even a few, brief, Pre-lithium XPs requiring *research-grade* plasmas may require 3-6 weeks of conditioning before suitable NBI plasmas are obtained (No TMB; using only HeGDC). For example:
 - discharges to finish FY 2010 Joint research milestone using bake calibrations for the IR thermography. (Plan is to have 2-color IR ready, but availability at the beginning of the run is uncertain).
 - a few days of work before lithium, e.g. high delta discharges with drsep variation, high I_p , and Bt scan, some at constant q95.

In This Scenario, Pre Lithium Phase is Only Long Enough to Bring Up All Systems Required for Start of LLD Commissioning



Decision Tree: After Bakeout While Awaiting Subsystems and Diagnostics to Get Ready for Commissioning

- **Assume LLD has passed the engineering ISTP (side 3), no TMB, try HeGDC**
 - 1) **Aim for high triangularity ohmic D diverted plasmas ~ 1-2 days of fizzles.**
 - 2) **If fizzles continue for 3rd day, try ohmic He diverted plasmas.**
 - 3) **If fizzles continue consider more HeGDC**
 - 4) **Check H/D and O/C of ohmic plasmas with VIPS2, SPRED, LOWEUS and XEUS.**
 - 5) **Continue ohmic plasmas to see if impurities decrease.**
 - 6) **As soon as suitable NBI target plasma achieved, start high triangularity NBI**
 - 7) **If subsystems and diagnostics ready, start lithium deposition and LLD commissioning.**

Planned LLD-Related External Startup Diagnostics

- **Visible Cameras**
 - **Phantom-V710, Bay-E, Top re-entrant window**
 - **Phantom-V7.3, Bay-J, Top re-entrant window**
- **IR Cameras**
 - **Fast IR Camera, Bay-H Top**
 - **Slow IR Camera, Bay-I Top**
 - **Slow IR Camera, Bay-G Bottom**
- **Lyman- α Diode Array**
- **Divertor Region Sample Probe**
- **3 Quartz Deposition Monitors**

Automated IR Camera Calibrated Temperature Waveforms Needed Between Discharges

Li thermal conductivity is low. (~ W/m-°K 400 Cu, 150 Mo, 45 Li, 15 SS)

- **Power Handling: SNL thermal analysis for cases with the strike point on the LLD with peak Li temperature set at 400 °C,**
 - can sustain a peak of ~2MW/m² for 10s and 4 MW/m² for ~3s.
 - Less Li, higher heat transfer.
- **Lithium evaporation from LLD is very high above 400°C and LiD starts decomposing. Need to monitor temperature profiles during NBI.**
 - LLD evap = LITER evap @ ~370°C
- **Automated IR Camera calibrated temperature waveforms critical to monitoring LLD operation and benchmarking thermal simulations against initially short low, low power, NBI on LLD.**

Near Term Startup Events

- **Preliminary Test Procedure (PTP):** While vented, end-to-end controls, instrumentation, PLC, and EPICS testing using mild heating of the plates (5-10°C).
- **Integrated System Test Procedure (ISTP):** Starts after pumpdown. Redo the PTP under vacuum prior to bakeout, during bakeout, after bakeout, and during initial plasma operations.
- **Commissioning:** Under controlled discharge conditions, obtain preliminary LLD performance data to meet FY10 Milestone, and qualify LLD for use as an operational tool for the duration of the 2010 Experimental Campaign.
- **Milestone:** a Liquid Lithium Divertor (LLD) will be installed in FY2010, and the relationship between lithiated surface conditions and edge and core plasma conditions will be determined. To understand pumping, D retention will be studied as a function of surface conditions such as: Li coverage and LLD surface temperature, and plasma exhaust parameters such as: scrape-off layer density, temperature, strike-point location, and flux expansion.

Summary of Key Timeline for Discussion

- LLD tested in air before pumpdown (room temp+10°).
- LLD tested in vacuum prior to Bake (350°C).
- Bake for 3 weeks.
- LLD tested during Bake (360°C).
- LLD tested after cooldown at initial operation temperature (205°C).
- Important to start with clean LLD (unclogged porosity) to maximize wetting.
- No Boronization to clog LLD porosity.
- D and He Startup plasmas for ~1 week or until required subsystems online.
- Start Commissioning: Turn on LITER, start loading LLD, get Milestone data.
- All XPs scheduled so as to fit into the LLD loading plan.
- At end of run, raise LLD temp to 400-500°C to unload Li.