

# PSI-issues in EAST

J.L. Chen, X.Z. Gong, G.N\_Luo,  
Y.Yang, J.S. Hu, J.G. Li and EAST team

Jlch@ipp.ac.cn

*Institute of Plasma Physics, Chinese Academy of Sciences  
P. O. Box 1126, Hefei, Anhui, 230031 China*



## Outline

- Introduction
- EAST experimental setup
- Primary PSI-issues and results
- Next experimental plan
- Summary
- Acknowledgements



# Introduction

HT-7/EAST

ASIPP

## Main Parameters of the EAST

	Nominal	Upgrade
$B_0$	3.5 T	4.0 T
$I_p$	1 MA	1.5 MA
$R_0$	1.7 m	1.7 m
$a$	0.4 m	0.4 m
$R/a$	4.25	4.25
$K_x$	1.2-1.5	1.5-2
$\delta_x$	0.2-0.3	0.3-0.5


### Heating and Driving:

ICRH	3 MW	6 MW
LHCD	3.5 MW	8 MW
ECRH	0.5 MW	1.5 MW
NBI		8 MW

Pulse length 1000 s

### Configuration:

Single-null divertor  
Double-null divertor





# What's new for the EAST

HT-7/EAST

- Experimental Advanced Superconducting Tokamak (EAST) is one of seven National Mega-Projects of Science Research under construction in China;
- Feb-Mar, 2006, 1<sup>st</sup> engineering commissioning. From July 25, 2006, on 2<sup>nd</sup> engineering commissioning and 1<sup>st</sup> physics experiment started before the last IAEA conference;
- National examination on the project just passed on Sept. 28, 2006, mainly testing some key design parameters and plasma breakdown;

## ➤ Achievements of the device



SC coils NbTi CICC-14kA-3.5T-4.5K

Height 10m

Diameter 8m      LHCD 2.45GHz, 2MW

Weight 414 ton      2.45GHz, 1.5MW

$P_{bg}$   $10^{-7}$  Torr      ICRH: 30-110MHz 1.5MW







## 1st experimental campaign in 2006

HT-7/EAST

- **March 2006: first engineering commission**
- **Middle of July: accomplishment of in-vessel components installation**
- **End of July: cooling down (60~80 K)**
- **5 August: GDC discharge followed by RF plasmas for wall cleaning**
- **20 September: cooling down ( magnets 4.5 K)**
- **22 September: accomplishment of engineering test (TF –up to 3.55T).**
- **23 September : null field configuration, break down with He**
- **26 September 2006: 1<sup>st</sup> boronization, first hydrogen plasma, pre-programming controlled:  $I_p \sim 220 \text{ kA}$ ,  $t \sim 2.7 \text{ s}$**
- **29 September : current feedback control**
- **30 September: discharge break for testing spare turbines**
- **2 October: 2nd boronization, density feedback control**
- **5 October: current and radial position control, followed by Z control**
- **8 October: 3rd boronization,  $I_p \sim 500 \text{ kA}$ , (shaping preparation)**
- **13 October 2006: elongated plasma ( $\kappa \sim 1.28$ )**







## 2nd experimental campaign in 2007

HT-7/EAST

- 20 December 2006: vacuum system start up
- 22 December: pumping of in-vessel vacuum
- 24 December: cooling down
- 9 January 2007: cooling magnets to 4.5 K
- 10 January 2007: PF coils & power supply system test
- 11 January: engineering test (TF coils + ICRF cleaning)
- 14 January 2007: break down with LHW (shot number 2729#)
- 17 January: pre-programming controlled:  $I_p \sim 200\text{kA}$  limiter 3157#
- 18 January: feedback control of  $I_p \sim 300\text{kA}$  limiter plasma 3231#
- 20 January 2007: IC coil test for vertical instability 3331#
- 22 January:  $I_p \sim 200\text{kA}$  double-null divertor plasma 3478#
- 8 February 2007: double-null divertor plasma of  $I_p \sim 500\text{kA}$  shaping during  $I_p$  ramp-up 4582#
- 9 February: long pulse 200kA/8.5s divertor plasma 4611#, optimization of low  $V$  ( $\sim 3.5\text{V}$ ) start-up 4654#
- 10 February: end of plasma experiment 4774#
- 11 February 2007: wall conditioning





## Outline

- Introduction
- EAST experimental setup
- Primary PSI-issues and results
- Next experimental plan
- Summary
- Acknowledgement



ASIPP

# All metal PFCs and arrangements

HT-7/EAST

Mo limiter

LHW launcher



GDC anode

ICRF antenna






ASIPP

HT-7/EAST

# Plasma diagnostics system








# ICRF system (30 kW)

HT-7/EAST

- 5 MW will be available (30~110MHz, first for HT-7);



HT-7



EAST



ASIPP

## Exp conditions in 2<sup>nd</sup> campaign

HT-7/EAST

- **Full metal PFCs, stainless steel in-vessel components, including liners, diverter plates, internal coils, RF antenna;**
- **Two movable molybdenum (Mo) limiters installed at  $R = 2.235\text{m}$ , with  $a_{\text{max}} = 0.45\text{ m}$ ;**
- **About 15 basic diagnostics for plasma study on EAST;**
- **Plasma control system (PCS) built in collaboration with DIII-D;**
- **RF systems at ICRF (30 kW) and at LHF (180 kW) for wall conditioning and discharge pre-ionization;**
- **Wall conditioning: baking, GDC and RF discharges, boronization.**



## Outline

- Introduction
- EAST experimental setup
- **Primary PSI-issues and results**
- Next experimental plan
- Summary
- Acknowledgement



ASIPP

# HT-7 vs EAST

HT-7/EAST

## HT-7

- Limiter configuration;
- 20% walls are covered by doped graphite with SiC coating;
- D<sub>2</sub> plasma operation;
- Plasma facing areas ~12m<sup>2</sup>;
- Low pumping speed;
- RF antenna for both wall conditioning and heating.
- GDC: 2 Mo anodes, ~2A/anodes, Movable.
- Baking: By electric resistance heating.
  - Highest Temp.
    - For liners is 250<sup>0</sup>C;
    - For limiter is 200<sup>0</sup>C.

## EAST

- Divertor configuration;
- All mental wall (SS+Mo limiter);
- H<sub>2</sub> plasma operation(60-70% H in the RG);
- Plasma facing areas ~50~60m<sup>2</sup>;
- High pumping speed;
- Specially designed RF antenna for wall conditioning.
- GDC: 4 SS anodes (use 2 fixed), ~2A/anodes,
- Baking: By hot N<sub>2</sub> interlayer heating; Electric resistance heating.
  - Highest designed Temp. for PFCs is 350<sup>0</sup>C;
  - Actually used :
    - PFCs ~150<sup>0</sup>C.
    - Windows <120<sup>0</sup>C.



## Pre-wall conditioning in winter of 2006

- 12/24 start pumping;
- 12/28 start baking, then gradually use cryopumping;
- Baking temperature at interlayer:
  - 12/28~1/2(4.5days) 120~140°C;
  - 1/2 baking temperature reduction;
  - 1/2~ (11days) 80~100°C;
- Baking temperature at pumping ducts;
  - 12/28~1/4(6.5days) 120~150°C;
  - 1/4 ~ 20~30°C。
- Baking temperatures at windows<120°C;
- During He-GDC, stop windows baking, and keep interlayer and pumping ducts baking; He-GDC ( to 1/13 16:00 total 70hours)
- He-ICR ( to 1/13 16:00 total 2h45m)




## He-GDC and He-ICR in EAST

- He-GDC
  - Dominant before plasma discharge;
  - 3~5h per night before plasma operation.
- He-ICR
  - Between plasma discharges;
  - System experiments
    - ✓ Three times;
    - ✓ Influence factors of power, pressure, magnetic field, pumping speed and wave duty time
  - Power: 3~20kW
  - Pressure: 4E-3Pa~10Pa




# Typical He-GDC and He-ICR


HT-7/EAST




He-GDC(3Pa, 2x2A)



He-ICR at early operation ( $1.2 \times 10^{-2}$  Pa, 15kW)



He-ICR with different power and pressure  
( $4.5 \times 10^{-3}$ - $1.8 \times 10^{-2}$  Pa, 3-20kW)



Inter shot He-ICR ( $4.5 \times 10^{-3}$  Pa, 10kW)






ASIPP


# He-ICR before and after oxidation

HT-7/EAST

1.4x10<sup>-2</sup>Pa 20kW He-ICR Before Oxidation



1.4x10<sup>-2</sup>Pa 20kW He-ICR after oxidation







- After He/O-ICR experiments, He-ICR is effective for oxygen removal;
- H and Impurities removal in He-ICR cleanings depended on wall conditions;
- H<sub>2</sub> was effectively reduced by He/O-ICR cleanings.



ASIPP

# Removal rates of He-ICR

HT-7/EAST





## He-ICR in EAST

HT-7/EAST

- **Successfully carried out ICRF WC with a specially designed antenna in a divertor machine-EAST;**
- **The removal efficiency for H in low pressure( $4.5E-3Pa$ ) He-ICR is almost as the same as in He-GDC cleaning ( $2Pa$ );**
- **Factors influence on He-ICR efficiency:**
  - **Results from partial removal rate and CCD pictures showed that the influence of TF (1-2T) was small;**
  - **Pulsed RF WC with wave duty time at 0.3s/1.2s,1s/2s is good;**
  - **High ICRF power promote particles removal;**
  - **He-ICRF is beneficial for impurities removal in early operation and after oxidation experiments.**
- **Require to increase pump speed at high pressure in EAST;**
- **Comparison with HT-7 results**
  - **Breakdown pressure different: HT-7 limited  $<0.2Pa$ , EAST reached  $\sim 10Pa$ ;**
  - **Power different: HT-7 reached 60kW; Highest RF power in EAST was used only 20kW(will be extend to high power in near future.);**
  - **Highest H removal rate is higher than HT-7 by a factor of 4.**



ASIPP

HT-7/EAST

## Primary results of oxidation in EAST


### Procedures

	Pressure	Power	Gas	Note
1	1.4E -2Pa	20kW	He-ICR	Wall temp.~150°C RF duty: 0.3s on/ 1.2s off B during RF cleaning: 1T; He:O <sub>2</sub> ~1:1
2	1.4E -2Pa	20kW	He-ICR	
3	1.4E -2Pa	5kW	He/O-ICR	
4	1.4E -2Pa	10kW	He/O-ICR	
5	1.4E -2Pa	20kW	He/O-ICR	
6	5E-2Pa	20-10kW	He/O-ICR	
7	7E-2Pa	10kW	He/O-ICR	
8	1.4E -2Pa	5kW	He/O-ICR	
9	1.4E -2Pa	20kW	He-ICR	
10	0.5Pa	4A*300V	He-GDC	
11	0.5Pa	4A*300V	He/O-GDC	
12	0.5Pa	4A*300V	He-GDC	



# He/O-ICR cleaning


HT-7/EAST




1. During oxidation, C was removed by the formation of CO and CO<sub>2</sub> and most of hydrogen released in the form of water molecules;
2. CO, CO<sub>2</sub> and H<sub>2</sub>O production after oxygen injection (Thermo-oxidation) only sustained for a short duration.
3. He/O-ICR are beneficial for long removal for C and H.
4. Higher power and/or higher pressure in He/O-ICR, more CO and H<sub>2</sub>O produced.



# Average removal rates in He/O-ICR



$1.4 \times 10^{-2}$  Pa



10kW


1. O-RF on a SS walls are beneficial for both H and C removal. Highest removal rate are  $7.8 \times 10^{22}$  H-atoms/h,  $4.2 \times 10^{22}$  C-atoms/h (20kW,  $7 \times 10^{-2}$ Pa)
2. Higher than that in He-ICR by a factor of 5 and a few tens respectively.
3. High pressure and conditioning power are favorable for removal of H and C.



ASIPP

# Comparison between EAST and HT-7

HT-7/EAST



HT-7: More  $O_2$  consumed, relatively more O reacted with C  
EAST: Less  $O_2$  consumed, relatively more O reacted with H



# He/O-ICR between EAST / HT-7

HT-7/EAST

## ASIPP

- Similar behaviors during oxidation.
- In both devices, H, C removal rates were higher than that in He-ICR by a factor of 4~6 and a few tens.
- Similar influence of power, pressure and wall conditions.
- High removal rates in EAST than in HT-7.
- In EAST, fewer O<sub>2</sub> consumed, higher fraction of O<sub>2</sub> reacted with H.
- Lower O retention rates (min<sup>-1</sup>.m<sup>2</sup>) than HT-7 by a factor of >10.
- With the same parameters(20kW, 0.014Pa He/O-ICR)
  - HT-7: ~2x10<sup>21</sup> H/hour; ~1.9x10<sup>21</sup> C/hour.
  - EAST: ~2.5x10<sup>22</sup> H/hour; ~1.3x10<sup>22</sup> C/hour.
    - Power density (20/40 vs 20/5 kW/m<sup>2</sup>)
    - Pumping speed (10<sup>4</sup> l/s vs 850 l/s)
    - Areas facing plasma (50~60m<sup>2</sup> vs ~12m<sup>2</sup>)
    - Volume of vessels(~ 40m<sup>3</sup> vs ~ 5m<sup>3</sup>)
    - Plasma facing materials (Stainless steels vs doped graphite (or SiC))
    - ICRF antenna (Shape, location.....)
    - Structure of vessels (Divertor vs Limiter)
    - Plasma fuels(H<sub>2</sub> vs D<sub>2</sub>)







# Breakdown Vloop and dIp/dt ramp-up rate



HT-7/EAST

ASIPP

$3.5 \text{ V} < V_{loop} < 6.5 \text{ V}$



$0.1 \text{ MA} < dI_p/dt < 0.65 \text{ MA/s}$








# First plasma on EAST

HT-7/EAST

ASIPP



Mo limiter





- After several breakdown shots, plasma current was very smoothly ramped up to 150 kA at a rate of about 0.5MA/s by pre-programmed control and up to 220 kA after only a few more shots. Circular cross-section H plasma with Mo limiter on Sept.26, 2006;
- To avoid impurity burn through, plasma density was relatively low, about  $0.4 \sim 1.0 \times 10^{19} / \text{m}^2$ . Strong HXR was observed;
- Most disruptions were due to the shift of plasma position. Even for the worst disruption, the induced voltage at the ends of the PF coils was very low due to the shielding effect of the vessel, safe for PF coils.



ASIPP


# Divertor probes

HT-7/EAST




# Inner divertor target


Electron temperature  $T_e$  (eV), Shot :4102




Electron density  $n_e$  ( $10^{18}/m^3$ ), Shot :4102




Particle flux  $\Gamma$  ( $10^{22}/m^2s$ ), Shot :4102




Heat flux  $Q$  ( $MW/m^2$ ), Shot :4102




EAST tokamak EFIT , Shot :4102





EAST tokamak EFIT , Shot :4102




EAST tokamak EFIT , Shot :4102




EAST tokamak EFIT , Shot :4102

Electron temperature  $T_e$  (eV) , Shot :4102



EAST tokamak EFIT , Shot :4102



EAST tokamak EFIT , Shot :4102




XUVSignal ShotNo:4098



**XUV**


Divertor configuration,  
reduction of core radiation of XUV




Down inner diveror target

4165#


CCD




Ha



XUV



Limiter configuration, enhancement of XUV radiation



Limiter configuration, enhanced radiation of impurity













## Outline

- Introduction
- EAST experimental setup
- Primary PSI-issues and results
- **Next experimental plan**
- Summary
- Acknowledgement



# UFO in vacuum vessel

HT-7/EAST





# Strategy for PFM development

All doped graphite with thick SiC coatings  
as plasma facing materials


Mechanically plus braze joined to heat sink

Reliable and convenient for primary plasma discharge and shape control

(1) Doped graphite (FW) +thick W on copper alloy as HHF PFCs

(2) All carbon based PFM? Doped graphite(FW) + CFC as divertor target

Change to all tungsten based PFCs  
W coatings on CLAM+W coatings on copper alloy



Internal cryopump

Passive stabilizer

Fast feedback Control coils

FW at LFS

FW at HFS

Baffles

Targets

Dome



$I_T=8.0\text{kA}$

## He-ICRF wall conditioning

1)  $B_V+B_T$

$B_V\sim 100\text{-}200\text{G}; B_T\sim 2\text{T}$

2) He+H<sub>2</sub>

H<sub>2</sub>/He  $\sim 0.2\text{-}0.3$

3)  $f_1+f_2$

$f_2>f_1$

4)  $B_T$ - Scan

$f_{\text{Generator}}$  scans!!



# Summary

HT-7/EAST

- **Divertor plasma has been achieved successfully in 2007 on the EAST superconducting tokamak with all metal PFCs;**
- **RF also have been successfully carried out for wall conditioning, recycling control between shots, oxidation and boronization;**
- **Much better results have been obtained compared with those in HT-7, and the basic data will be compared with **full C** condition;**
- **ICR conditioning techniques will be carried out in EAST under **full C** and mixed material with **C/W** conditions;**
- **Towards long-pulse high power plasmas, **full graphite wall and PFC** with **high power** heating (3.5MW LH+IC) and **new diagnostics** will be available in the 3rd experimental campaign;**
- **For the divertor configuration, RF wall conditioning still need to be further developed.**



# Acknowledgements

- We would like to thank the EAST team and Dr.J.Leuer, Dr.A.Hyatt (GA), Dr.D.Mueller (PPPL), Prof.T.Watari, Dr.N.Ashikawa (NIFS), Dr.H.Takenaga (JAEA), and Prof.K.Nakamura (Kyushu Univ.) for excellent experimental study;
- This work was partly supported by JSPS-CAS Core-University Program on Plasma and Nuclear Fusion.