



U.S. DEPARTMENT OF
ENERGY

Office of
Science




Overview of Initial Operation of NSTX-U

Devon Battaglia

On behalf of the NSTX-U Team

TOFE Conference
Philadelphia, PA
August 22, 2016





Outline


- NSTX-U mission toward advancing magnetic confinement fusion development
- Highlights from the first NSTX-U experimental campaign
- Initial operations with plasma control and digital coil protection systems on NSTX-U

NSTX Upgrade advances the spherical tokamak (ST) concept and complements larger aspect ratio devices

- Explore unique ST parameter regimes to advance predictive capability
- Develop solutions for the plasma-material interface challenge
- Advance ST Fusion Nuclear Science Facility (FNSF) and reactor concepts




Aspect Ratio $R/a = 1.4, 1.7, 2.7$




NSTX completed multi-year upgrade to increase field, heating and pulse length

Previous center-stack **New center-stack**



TF OD = 20cm **TF OD = 40cm**



Present NBI **New 2nd NBI**


- National Spherical Tokamak operated 1999 - 2010
- New center column: double toroidal magnetic field, triple solenoid V-s
 - Access to $2 \times$ higher temperatures, lower collisionality
 - Pulse lengths increase $1 \rightarrow 5$ seconds
- Second neutral beam injection system added
 - Doubles NBI heating and increases flexibility in heating profile
 - More tangential injection triples NBI current drive and increases current profile control capability
- Increased flexibility in divertor field to support innovative configurations

Outline

- NSTX-U mission toward advancing magnetic confinement fusion development
- **Highlights from the first NSTX-U experimental campaign**
- Initial operations with plasma control and digital coil protection systems on NSTX-U

NSTX-U recently completed its first experimental campaign

- First plasma August 10, 2015
 - Signified completion of major construction
- First experimental run from December, 2015 to June, 2016
 - Commissioned control, heating and diagnostic systems
 - Began physics assessment of new capabilities
 - Run ended early due to an internal short within a divertor coil
 - Currently removing coil for inspection and defining corrective actions
- Next campaign slated to begin mid-2017 following coil replacement
 - Restart with new capabilities, including full-field operation at 1 Tesla



One of the first H-mode discharges on NSTX-U
January 13, 2016
(second week of operation)


Majority of commissioning activities were completed or nearing completion at the end of the campaign

- XMP-101: Breakdown Optimization
- XMP-102: Gas Flow Rate Calibration
- XMP-106: Magnetics Calibration
- XMP-126: I_p and R Control
- XMP-105: Software Tests for n=0 Control
- XMP-115: ISOFLUX Commissioning
- XMP-116: Initial H-Mode Access
- XMP-127: Neutral Beam Commissioning
- XMP-107: Neutron Calibration Transfer
- XMP-120: Strikepoint & X-Point Control
- XMP-128: Increase L-Mode Elongation
- XMP-132: Fast Rampdown Sequence Commissioning
- XMP-137: Increase κ and I_p in L- and H- Mode
- XMP-138: Improved Vertical Control Checkout
- XMP-121: SPA & RWM Control Checkout
- XMP-140: PF-5 Proportional EFC Test
- XMP-141: Proportional EFC Tests
- XMP-111: MPTS Commissioning
- XMP-142: Reduced MHD H-Mode Development
- XMP-146: Higher-Order Feed Forward EFC in L-Mode
- XMP-147: Integrate control improvements in L-Mode fiducial
- XMP-148: Between-Shot TRANSP Validation
- XMP-110: ssNPA & FIDA checkout
- XMP-150: He Density Scan for Z_{eff} Calibration
- XMP-151: L-Mode Development for Core and Boundary XPs
- XMP-152: Improved dr-sep and rtEFIT Control
- XMP-153: H-mode Access and Rampup Control Development
- XMP-154: Inner Gap Control Development
- XMP-114: CHERS Modulation Study
- XMP-125: MSE-CIF 2nd NB Interference Study
- XMP-130: Granule Injector Commissioning
- XP-1506: Low Beta n=1 EFC

Completed
In progress
Planned


Commissioning activities developed discharges to support planned experiments

- Rapid development of high-performance discharges in first 10 weeks of operation
 - Operated routinely at $B_{T0} = 0.65T$, greater than maximum NSTX field
 - Wall conditioning: Helium GDC + boronization
 - Many diagnostics available at first plasma
- Stationary L-mode pulse length ~ 4 times longer than NSTX
 - Supported first experiments on error fields, transport, current drive and fast-ion physics
- H-mode discharges comparable to NSTX performance for $I_p < 1.0$ MA




Neutral beam injection using the new beam line immediately demonstrated exciting results



- Plasma instabilities are driven by neutral beam heating
 - Instabilities can increase the transport of thermal energy
 - Example at right, instabilities start with when NBI heating is increased
- Tangential injection suppresses fast ion instabilities
 - Unique result to observe instabilities go away after adding more power
 - Significant tool for improving energy confinement



Steady progress in error field correction, plasma control and NBI heating improved H-mode performance





- 202946 Feb – no EFC
- 203679 March – EFC v1
- 202112 April – EFC v2
- 202118 April – EFC v2



H-mode scenario achieved with $H_{98y,2} > 1$ and $\beta_N \geq$ no-wall stability limit

- Scenario matches best NSTX performance at $I_p = 0.9$ MA
 - Progress toward larger I_p and longer pulses was interrupted by coil failure




Outline

- NSTX-U mission toward advancing magnetic confinement fusion development
- Highlights from the first NSTX-U experimental campaign
- **Initial operations with plasma control and digital coil protection systems on NSTX-U**


Shape control challenges due to increased aspect ratio (A) of NSTX-U were successfully addressed

Higher-A operation challenges ...

- Vertical stability
 - Improved detection of vertical plasma motion
 - Achieved comparable elongation to NSTX at matched I_i
- Controlling inboard gap without inboard PF coils
 - Coil actuator sharing algorithm (MIMO): find solution that best matches target shape when # control points > # PF coils




Modify the plasma shape to achieve the best match 8 plasma shape target points (including inboard gap) with only 7 PF coils.





Plasma Shutdown scheme routinely used to initiate controlled rampdown of NSTX-U discharges

- **NSTX**: No means of detecting a disruption, or ramping down the plasma current based on events.
- **NSTX-U**: State machine orchestrates the shutdown.
 - Examples of events triggering shutdown:
 - Ohmic coil approaching current limit (loss of control)
 - Loss of vertical stability (example at right)
 - Plasma current missing target
 - Insufficient plasma current for control
 - Routinely used in NSTX-U discharges to avoid disruptions
- Supports future research into reactor-relevant disruption avoidance schemes
 - Disruption avoidance may be critical to future divertor material testing on NSTX-U



Digital coil protection system (DCPS) successful in avoiding coil force and heating limits

- DCPS developed to protect coils from exceeding force and thermal limits
 - 400 real-time force and stress calculations using coil and plasma currents
 - Fault detection triggers all power supplies to remove voltage from coils
- System designed for every-shot protection
 - Redundant systems with multiple layers of system status checking and fault tracing
- DCPS successfully avoided exceeding force limits during off-normal events



Summary

- NSTX-U is now the most capable spherical tokamak in the world fusion program
 - NSTX-U will evaluate the ST design for future burning plasma devices and complement conventional tokamak experiments
- Initial operations made rapid progress in discharge scenario development and commissioning heating and diagnostic systems
 - Long (> 1.5 s) L-mode discharges supported first experimental results
 - Progress in H-mode scenario enabled by progress in error field correction, shape control and heating power availability
- New plasma control and coil protection systems were commissioned to support NSTX-U operations
 - Many of the new capabilities applicable to present and future tokamak devices

NSTX-U Talks and Posters at TOFE 2016

- Thermal and structural performance evaluation of the NSTX-U high-z divertor
 - Art Brooks 18403 Monday Poster Session
- NSTX-U 2nd Neutral Beam Relocation
 - Neway Atnafu 18167 Monday Poster Session
- NSTX-U Bake-Out Simulations and Evaluations
 - Peter Titus 18220 Monday Poster Session
- Design and operation of the electrical noise suppression system for CHI on NSTX and NSTX-U
 - Zhi Gao 18163 Tuesday Poster Session
- Studies of Next-Step Spherical Tokamaks Using High-Temperature Superconductors
 - Jon Menard 18205 Tuesday AM Invited Talk

Please come tour NSTX-U on Tuesday evening!