

Supported by



# NSTX Facility Plan

Masayuki Ono  
For the NSTX Team

NSTX Research Forum  
Nov. 28-29



Los Alamos  
NATIONAL LABORATORY



# Facility Plan Outline




- Facility Overview (Diagnostics covered by Bob Kaita)
- Sub-Systems
  - Magnets
  - NBI
  - RF (HHFW/EBW)
  - CHI
  - Error Fields
  - Impurity Control
  - Particle Fueling
  - Plasma Control System (Dave Gates)
  - I&C Infrastructure
- Summary

# NSTX Facility Has Continued Rapid Progress in Operational and Experimental Capabilities



Nov 1, 2000



## Baseline Parameters

(Achieved)

Major Radius 0.85 m

Minor Radius 0.68 m

Elongation = 2.2 (2.5)

Triangularity = 0.6 (0.7)


Plasma Current  
1 MA (1.4 MA)

Toroidal Field  
0.3 to 0.6 T ( $\leq 0.45$  T)

Heating and CD  
5 MW NBI (5 MW)  
6 MW HHFW (6 MW)  
0.5 MA CHI (0.39 MA)

Pulse Length  
= 5 sec (0.5 sec)

# Fisheye View of NSTX Vacuum Vessel Interior



Passive  
Plates


NBI  
Armor

HHFW  
Antenna  
Array

Center-  
Stack

Aug. 2001


# NSTX Facility status (●) and Plans (◆)



# Facility plan developed to maximize the FY02 research output within the budget constraints.



- Achieve twelve run weeks between Jan. 14 and May 3. “Three-run-weeks followed by one-maintenance-week” is a very aggressive schedule leaves little schedule contingency.
- Minimize technical and engineering activities (and expense) in July and Aug. Potential skill-mix problem.



# Status of Magnet Systems



## Existing Capability:

- PFs (1B, 2, 3, and 5) and OH running routinely at full rating.
- TF ran routinely at 4.5 kG but limited to  $t_{\text{pulse}} \leq 0.5$  sec due to an uncooled turn. The water leak repaired.
- PF 1A coil bi-polar power supply commissioned available.

## New Capability: (Next Run)

- A flourinert cooling system prepared for this run.
- Pulse length to be determined by the TF temperature rise (50 °C) allowable recommended by engineering for time being. The run will start with  $\leq 4.5$  kG and move up in the field as needed.
  - $B_T = 4.5$  kG ,  $t_{\text{pulse}} \leq 1$  sec
  - $B_T = 5$  kG ,  $t_{\text{pulse}} \leq 0.71$  sec
  - $B_T = 5.5$  kG ,  $t_{\text{pulse}} \leq 0.48$  sec
  - $B_T = 6$  kG ,  $t_{\text{pulse}} \leq 0.24$  sec

# NBI (Neutral Beam Injection) System Routinely Operation at 80 keV



## Existing Capability:

- Three ion sources (A,B, & C) operated routinely at 80 kV
- Total injection power of up to 5 MW
- Some modulation capability introduced
- One source went up to 90 kV.

## New Capability: (Next Run)

- Source C developed water leak but was repaired.
- High voltage up to 100 kV can be made available as needed.
- NBI system will be available on Jan. 21,2001.

# 6MW 12-Antenna HHFW System is Ready



- Visual inspection of HHFW antennas after the last run showed no damages.
- Power level (up to 6 MW) and reliability has been steadily improving.
- All sources checked into dummy load after minor repair and maintenance
- Preparing for operation with full antenna phase feedback
- Remote control of sources and feedback controllers
  - Complete control of HHFW power, phase and timing from NSTX control room

*Ready to begin current drive and pulse extension research starting January 14, 2002.*

# EBW / ECH

## Viability of EBW for local CD in NSTX?



### Existing Capability:

- ORNL ECH Preionization System (30 kW). Additional control and monitoring added to aid operation and troubleshooting
- EBW emission efficiency increased to 15 % from 5% during the L-H transition in NSTX.
- On CDX-U, near 100% EBW emission efficiency obtained with local limiter.

### New Capability: (Next Run)

- New EBW emission detector near the HHFW antenna providing local limiter with a goal of getting high emission efficiency. Investigate a possible (low cost) local limiter option.
- Understand the EBW emission with edge measurements and theory modeling.
- Need more theory/modeling for EBW CD performance and benefits.

# Impurity Control



## Existing Capability:

- Graphite tiles covering plasma contacting surfaces
- HHFW antennas “boxed-in” with BN plates
- Resistive heater to bake center stack tiles to 300°
- Hot water heater to bake outer VV to 150°C
- TMB Gas Boronization
- Between-shots He Glow
- Plasma Boronization
- Wall coupons

## New Capability: (Next Run)

- Compressed He Gas Bakeout system to bring graphite tiles to 350°C.
  - Thermocouples (53), IR Camera, metrology

## Future Capability:

- Boron/Lithium Pellet Injector (CY 02)

# Particle Fueling



## Existing Capability:

- Out-board gas injectors (High throughput but not efficient for core fueling)
- Neutral Beam Injection (Efficient but  $\leq 4 \times 10^{20}/\text{sec}$ )

## New Capability: (Next Run)

- In-board/mid-plane Gas Injection System
  - Essentially identical to the MAST system
  - Slow / uncontrolled injection due to low gas line conductance
- Real-time gas injection control system (Out-board injectors)

# Central I&C



- NSTX diagnostic fiber infrastructure of 100 channels was completed in FY01.
- EPICS (Engineering Control System Software) upgraded to a current version. This also allowed migration to Solaris 8.
- A new disk storage cabinet with total of 144GB. This cabinet will provide two SCSI channels for improved MDSplus throughput.
- NSTX data serving and archival was enhanced for a total of 360GB. Future expansion possible for additional 1-2TB.
- Further acquisition time speed up being introduced.

# Error Fields



## Existing Capability:

- Locked-mode detector revealed PF 5 coil position error.
- The position error confirmed by direct measurements.

## New Capability: (Next Run)

- New PF 5 Coil Alignment Clamps being installed.
- The alignment result to be checked with locked mode coils.

## Future Capability: (Within one year)

- Finer field error corrections?
- Feedback coils?

# Summary



- NSTX Facility has been rapidly ramping up. Many new capabilities implemented.
- The facility improvements to support FY 02 research goals.
  - Impurity reduction
  - Improved fueling
  - Error fields reduction
  - Longer TF pulse length
  - Higher TF capability
  - Improved plasma control, data acquisition systems
  - Improved heating and CD systems reliability
- Budget is very tight. Maintain the schedule is crucial.
  - Plasma Operations: Jan. 14 - May 3.
  - MSE/CHERS/X-ray Opening: May - June
  - Minimum activity months: July - Aug. to conserve fund.
  - Sept. as optional month for start of plasma operations for MSE.