

Report on ET2 (HHFW) Research

J. R. Wilson

NSTX Research Forum

Jan. 31 - Feb. 2, 2000

PPPL


Princeton NJ

Goals of HHFW Phase 1 Research


- 1 Understand the operation of the HHFW Antenna System
- 2 Understand where the HHFW power goes
- 3 Be prepared to begin CD Experiments

- We have a good start on goal 1
- We also have data on goal 2
- Goal 3 will be explored this summer/fall

HHFW Antenna Installed




Each transmitter drives pair of antennas in resonant loop configuration



Preliminary setup with two transmitters and eight antennas

RF enclosure

NSTX test cell



- 8 current straps
- 4 resonant loops
- 2 power dividers
- 2 quarter wave transformers
- Strap 0-6, 1-7, ... connected in resonant loops

- Electrical length of each loop is 2λ


POWER FEED AND SPLITTING ARRANGEMENT

Upper Loops
7-10

1/4 Wave
XFMR and
Feed line

5 Way Cubes

Lower Loops
1-4



ET2 Run Summary

- 1 XMP brought system into operation - 2 days
 - 11/11, 12
 - Up to 400 kW short pulse (0.03 s) with 1 transmitter and 4 antenna straps
- 1 XP explored coupling and preliminary heating - 6 days
 - 12/9, 10
 - Removed $\lambda/4$ transformers -loading as measured in piggy back mode was too high
 - Power up to 660 kW (0.03 s) with 2 transmitters and 8 antenna straps
 - Loading studies - density scan, gap scan
 - $0-\pi-\pi-0$ phasing ($k_{\parallel} \sim 7 \text{ m}^{-1}$)
 - 12/14, 15
 - Power to 1 MW (0.07 s)
 - Phasing changed to $0-\pi-0-\pi$ ($k_{\parallel} \sim 14 \text{ m}^{-1}$)
 - Plasma position varied
 - 1/10, 11
 - Power to 2 MW (0.04 s) 1.6 MW (0.07 s)
 - AM power for heating studies - 100 Hz square wave up to 1.6 MW for (0.1 s)
 - Both antenna phasings applied

Goals of Phase 1 Research as Expressed at last years Forum and Status

- Bring system into operation
 - Partial System used during this run
 - 8 of 12 antenna elements
 - 2 of six transmitters
 - All antenna diagnostic signals
 - Two fixed phasings available - $0-\pi-\pi-0$ and $0-\pi-0-\pi$
 - 2 MW power goal met
 - Voltage is not a limitation
- PLASMA LOADING HIGHER THAN EXPECTED
REQUIRING REMOVAL of $\lambda/4$ TRANSFORMERS

Goals and Status

- Establish Baseline Properties of Antenna Array

- Vacuum condition to 20 kV 0.5 s

- ☞ **Achieved 25 kV 0.3 s**

- Vacuum conditioning was easy and fast and did not determine antenna performance in plasma. It was helpful in recovering from other operation quickly**

- Measure electrical properties of antenna (L,M,R) as a function of plasma density, edge location, shape, power, and phase and compare with theory

- ☞ **Have data for these analyses and have begun work**


- Density profiles seem broader than expected, little dependence with power observed. Only small change with phase observed. Larger changes seen with configuration**

- Define parameters for full power operation

- Vacuum Voltage limit not an obstacle**

- Plasma conditioning and MHD events more important**

Edge Density profile as measured by ORNL Reflectometer




101544

R=11 Ω

t= 160 ms

Edge Density profile as measured by ORNL Reflectometer




$R = 17 \Omega$

101544

$t = 175 \text{ ms}$

Edge Density profile as measured by ORNL Reflectometer




101544

$R = 23 \Omega$

$t = 190 \text{ ms}$

Loading
Calculation
0-p-0-p phasing



Times of
ne profiles

Time (s)

Goals and Status (cont.)

- Power Goals

- 2 MW half way through Phase 1  **Achieved**

- 4 MW at end of Phase 1

Requires some improvement in power handling with plasma and plasma response to power

Antenna- plasma interaction continued to improve with time

- Edge Physics

- Characterize rf power flow in scrape-off

-  **TV Camera showed little interaction on antenna**

-  **Have edge density profiles (needs analysis)**

**More work needed to see if power flowing to divertor region
Edge probe etc.**

Goals and Status (cont.)

- Heating

- Quantify heating efficiency using magnetics

- ☞ **More difficult to quantify than anticipated but still under analysis**

- Determine location of heating using USXR

- ☞ **On modulated shots, heating observed for $r/a \leq 0.4$ with $0-\pi-0-\pi$ phasing but not $0-\pi-\pi-0$**

- ☞ **Theory would predict this for low target temperature**

- ☞ **Given density and target temperature profiles we can try to model this**


- ⇒ **Absolute calibration needs new diodes**

Determine if ion absorption present


- ☞ **No diagnostic available yet - low apparent temperatures should not yield ion heating**

First signs of heating observed for $0-\pi-0-\pi$ phasing

900 kW rf



No rf



USXR data for HHFW experiments

- Three diode arrays with different filters

Filter	Energy range	Estimated spectral content	Position on NSTX
Ti 03 μm	$E > 0.1 \text{ keV}$	C V, C VI lines $E \approx 0.35 \text{ keV}$ + metallic (Cu) lines $E \approx 1.1 \text{ keV}$	Horizontal down
Be 10 μm	$E > 0.7 \text{ keV}$	Metallic lines $E \approx 1.1 \text{ keV}$	Horizontal up
Be 100 μm	$E > 1.4 \text{ keV}$	Continuum	Top


- T_e sensitive ratios:

Be 100 / Be 10 \approx continuum / metallic lines


Be 10 / (Ti 03 - Be 10) \approx metallic lines / carbon lines

- Impurity injection effects assessed in RF modulation experiment

Spectral response of USXR arrays




Central chord signals and ratio in OH and RF shots




- 60 % increase in Be 100 / Be 10 during first half of RF pulse
- Minor density increase
- Sudden emission drop before the pulse end

Evolution of the emission profiles



- Both mid and high energy signals peak during RF
- Emission drop at $t \approx 182$ ms occurs simultaneous in all chords (mild RE ?)


Reconstructed emissivity profiles at $t \approx 170$ ms



- Strong peaking of high energy emission during RF
- 150 % increase in Be 100 / Be 10 emissivity ratio on axis


Possible estimate of T_{e0} increase

$\frac{\text{Be 100} / \text{Be 10} (T_{e0})}{\text{Be 100} / \text{Be 10} (1 \text{ keV})}$





- Rough calculation of line integrated Be 100 / Be 10 ratio in C+Cu plasma
- Observed 60 % ratio increase may indicate up to 50 % T_{e0} increase

Amplitude Modulated Power Waveforms for Heating Study




Phasing $0-\pi-0-\pi$


RF modulated shot # 101921 (0- π , 0- π phasing)



- Strong increases in both the high-to-mid and mid-to-low energy ratios synchronous with the RF pulses suggest again core heating
- Slow ratio decay after 175 ms seen also without RF during the day





- Emission increase localized inside $r/a < 0.4$



MIST simulation of Cu injection in $T_{e0} = 1$ keV,
 $N_{e0} = 10^{13}$ cm $^{-3}$ plasma
 $D = 8$ m 2 /s

- Time scales for impurity effects much longer than those observed

RF modulated shot # 101933 (0- π - π -0 phasing)



- Significantly weaker modulation seen in 0- π - π -0 phasing shot
- Too poor statistics for a definite conclusion

Remaining Phase I Research

- Complete HHFW system hookup

Issues:

- **Do large values of antenna loading require a change in configuration ?**
- **Make phase control operational**
- Complete Heating study
 - **Heating at higher density, temperature**
 - **Raise power to max**

Issues:

- **Why does heating sometimes disappear?**
- **MHD? Radiated Power?**
- **Role of ion heating**

HHFW Summary

- Successful start of HHFW campaign
- 2 MW power milestone met
- Large data base of loading data acquired
 - **Edge density profiles will allow quantitative analysis**
 - **Loading resistance larger than expected**
- Heating observed under some conditions
 - **Centrally peaked electron heating ($r/a \leq 0.4$)**
 - **Only for slowest phase velocity**
 - **MHD or radiated power may terminate heating**