


Supported by



NSTX Facility and Budget Plans – FY03-05


In Support of the NSTX Research Program

Masayuki Ono

Princeton Plasma Physics Laboratory
For the NSTX National Research Team


Budget Planning Meeting – FY 2005
Office of Fusion Energy Sciences
Department of Energy

March 18-19, 2003
Gaithersburg, Maryland



Columbia U
Comp-X
GA
INEL
JHU
LANL
LLNL
Lodestar
MIT
Nova Photonics
NYU
ORNL
PPPL
PSI
SNL
UC Davis
UC Irvine
UCLA
UCSD
U Maryland
U New Mexico
U Wash
U Wisc
UKAEA Fusion
Hiroshima U
HIST
Kyushu Tokai U
Niigata U
Tsukuba U
U Tokyo
Ioffe Inst
TRINITI
KBSI
KAIST
ENEA, Frascati


NSTX Facility Capability Steadily Improved





Capabilities

<i>PFC bakeout</i>	350°C
<i>Gas fueling</i>	HFS/LFS
Aspect ratio	1.27
Elongation	2.5
<i>Triangularity</i>	0.8
Plasma Current	1.5MA
<i>Toroidal Field</i>	0.6T
<i>NBI (100kV)</i>	7 MW
HHFW (30MHz)	6 MW
<i>- full antenna phase control</i>	
<i>Pulse Length</i>	1s
<i>Reduced PF error field</i>	



Rapid Progress On High Beta Research



TF Fault Occurred on February 14, 2003



A TF "flags" joint separated.



Fortunately:

- No serious collateral damages occurred.
- TF bundle lifted out of machine without breaking high vacuum allowing important post diagnostic calibrations.

Lesson learned and move on



- o A joint design weakness uncovered by this incident and through detailed analyses. (loss of contact pressure, ambiguous load path, fatigue factor - joint failed in its 5th year of operation ~10,000 cycles.)
- o Improved joint with sufficient margin being designed including mock-up fatigue tests of 50,000 cycles.

- o TF Joint Final Design Review (inviting participants from C-MOD, MAST, DIII-D, PEGASUS, and FFOC) to be held in April.

- o Once the design is complete, the fabrication is relatively rapid.


- o The TF bundle fabrication can be funded within the operation budget.

- o Significant long term benefits with good joint design:
 - Improve long term operational reliability
 - Achieve routine operations up to full parameters
 - Reduce future maintenance and repair liabilities


NSTX Schedule



Original Plan



Revised Plan



- The outage is accelerated by three months.
- New plan allows FY 04 extended outage.
- Increase collaborations.*

- *- DIII-D (RWM, Fast Ion MHD, Confinement, Pedestal Physics, RF Operations)
- C-Mod (X-ray spectroscopy, Edge and Micro Turbulences, RF Operations, MSE)
- MAST (EBW, Boundary Physics, Confinement Scaling)
- Support ITER costing

MHD Mode Stabilization

Opportunity Areas are Resonant Field and RWM Controls.



Plasma
Operations

FY 03	FY 04	FY 05
-------	-------	-------

MHD Diagnostics

- Wall-mode sensors
- Fast X-ray cameras (Frascati, JHU, PSI)
- Ultra-soft x-ray arrays (JHU)
- Fast MHD sensor
- Improved magnetics and EFIT (Columbia)
- Real time EFIT (GA)

- $\beta_p \sim 0.9$, $V_{loop} \sim 0.2$ at 1 MA single null
- $\beta_N \approx 7$ and $\beta_p \approx 2.5$ during ramp down
- 1 MA with half-swing

Resonant Field Control

● Error Field Reduction

● Preliminary Resonant Field Control System (Columbia)

● Optimized Resonant Field Control System (Columbia)

- $\beta_T \sim 15\%$ higher than FY 02
- Locked mode occurrence reduced

Confinement and Transport

Exciting Opportunities For Advanced Fluctuation Diagnostics



Plasma
Operations

FY 03

FY 04

FY 05

Profile Diagnostics

• T_i , V_{\perp} , $V_{pol}(edge)$
with high precision.

● 51 Channel
Toroidal CHERS

● Edge Rotation
Spectrometer

● 4 Channel
FIReTIP(UCD)

● Poloidal
CHERS

● Extra 10 Channels
MPTS

● 7 Channel
FIReTIP(UCD)

● Third laser
MPTS

Energetic Particles

● Fast Ion Loss
Probe

Fluctuation Diagnostics

• Intriguing
fluctuation data
obtained

● Low k Reflectometer
(UCLA)

● Gas-puff Imaging
(LANL, PSI)

● Reciprocating probe (UCSD)

● Install Prototype High k
Microwave Scattering

● Install Low k
Imaging
Reflectometer

Non-Inductive CD Systems


Enhancement Opportunity areas are EBW and CHI



Plasma Operations

FY 03	FY 04	FY 05
-------	-------	-------

HHFW (6MW)
ORNL/VLT
GA,UCSD,
MIT




• Power improved to 5 MW from 3.5 MW in FY02

- Decision Point


- Base

EBW -E / -CD



1 MW High Power EBWCD Tube Development (Collaboration with MIT/ORNL/VLT)

CHI ($I_T = 0.5$ MA)
U. Washington
GA,LANL



• Absorber arcs reduced.

Boundary Physics

Exciting Enhancement Opportunity in Core Fueling and Boundary Physics



Plasma Operations	FY 03	FY 04	FY 05
-------------------	-------	-------	-------

Wall

Conditioning

(Gas/plasma Boronization, Between-shot GDC)

● Li/Boron Pellet Injector

- Decision Point
 - Base
 - Incremental

Power/Particle Control

● Divertor IR Camera (ORNL)

■ Fast IR Camera (ORNL)

Advanced Power and Particle Handling Decision Point (Divertor Cryo Panel)

• Dramatic divertor heat load spreading for high □

● AEUV Spectrometer
■

■ Divertor Thomson Scattering

Fueling

● In-board gas injectors ● Supersonic Gas injector

• Easier H-mode access confirmed

■ Pellet injector in "suitcase" (ORNL)

NSTX Facility Utilization



Facility Plasma Operations Availability

	FY 02	FY 03	FY 04	FY 05
# of run weeks planned	12	12	21	21
# of run weeks achieved	13*	4**		
# of hours	520	160	840	840

* 90% overall facility availability achieved in FY 02

** The facility operation was interrupted due to the TF fault problem in Feb. 2003.

Participating Research Personnel

	PPPL	non-PPPL
Researchers	42	70***
Post Doc.	3	7
Grad. Students	5	5
Undergrad. Students	3	5

*** Including 15 overseas collaborating researchers from countries Japan, Russia, Korea, UK, Ukraine, and Canada in FY 03

NSTX Budget Summary (\$M)




Facilities	FY03	FY04	FY04	FY04	FY05	FY05	FY05
Run weeks	12(4)	21	11		21	8	
	Base	Base	10% cut	Incr.	Base	10% cut	Incr.
Facility Operation	\$15.44	\$16.95	\$15.93		\$17.21	\$15.90	
CHI Absorber							
Error Field Coils	\$0.30	\$0.25	\$0.25		\$0.25	\$0.25	
Other Upgrades		\$0.50		\$0.54			\$1.49
Facilities Total	\$15.74	\$17.70	\$16.18	\$0.54	\$17.46	\$16.15	\$1.49

Science							
PPPL Research	\$8.28	\$9.30	\$8.34		\$9.44	\$8.40	
Upgrade Diag.	\$1.00	\$1.00	\$0.58	\$0.40	\$1.20	\$0.55	\$1.05
Colla. Diag. Interf.	\$0.62	\$0.70	\$0.56	\$0.10	\$0.60	\$0.56	\$0.10
Collaborations	\$4.30	\$4.77	\$4.30	\$0.27	\$4.77	\$4.30	\$0.27
Science Total	\$14.2	\$15.77	\$13.78	\$0.77	\$16.01	\$13.81	\$1.42

ERWM	\$1.68	\$1.71	\$1.71		\$1.71	\$1.71	
Grand Total	\$31.62*	\$35.18	\$31.67	\$1.31	\$35.18	\$31.67	\$2.91

*Note: FY03 Base includes ~ \$1.2M Carryover from FY2002.

NSTX PPPL Personnel Staffing



- Overall PPPL staff reduced by 79 in FY 2003.
- Some reductions in FY 04 and 05.
- Without D&D, reduced flexibility to reassign technical staff within PPPL.

Incremental Funding For FY 04 - 05 Can Greatly Enhance NSTX Science Output



- **Improve facility capability:**
 - Implement deuterium pellet injector (FY 04)
 - Start 1 MW EBW 15 GHz tube development (FY 05)
 - Divertor cryo-pumping particle control system (FY 05)
- **Improve Diagnostic capability:**
 - Fast infrared camera for boundary physics (FY 04)
 - Divertor MPTS (FY 05)
- **Improve facility reliability and availability**
 - Spare parts and preventive maintenance.

Consequences of 10% Budget Cut In FY 04



- Significant reduction in runtime (from 21 to 11 weeks)
- Research progress slowed by almost 50%.
- NSTX staff reduction of ~ 13% or ~ 15 FTE
 - Could result in further terminations due to severance cost
- Non-labor reduction of ~ 50%
 - Diagnostic components, spare parts, energy, travel, *etc.*
- Critical facility and diagnostic upgrades will be deferred.
 - HHFW antenna upgrade and CHI absorber null field coil power supply
 - Poloidal CHERS, Thomson scattering upgrades, Divertor Bolometer.
- Similar impact on all collaborations.

FY 05 impacted more severely due to inflation.

Summary



- FY 02 was a very productive year (one more run week than planned and 90% overall plasma availability.)
- FY02- 03 campaign produced very exciting results.
 - Record beta values achieved.
 $\beta_{\square} \approx 35\%$, $\beta_N = 6$, $\beta_N / I_i = 10$, $\beta_{\square_{pol}} > 1$.
 - High beta and high confinement ($\beta_N H_{89P} \approx 15$) sustained for \square -pulse $> \square$ -skin or 8 \square_E ($V_{loop} \sim 0.1V$).
 - Good progress on RWM, no wall beta limit exceeded by 30% and sustained for many resistive wall time through plasma rotation.
- FY 04-05 base budget allows significant increase in the run weeks from FY02- 03, crucial for making timely progress.
 - Improved TF will improve facility reliability and availability.
 - Physics capability rapidly ramping up to support exciting program.
 - Far more experimental proposals than run time available.

NSTX program is oriented to FESAC goals.