

NSTX Accomplishments and NSTX-U Research Plans in Support of Fusion Next-Steps

Coll of Wm & Mary
 Columbia U
 CompX
 General Atomics
 FIU
 INL
 Johns Hopkins U
 LANL
 LLNL
 Lodestar
 MIT
 Lehigh U
 Nova Photonics
 ORNL
 PPPL
 Princeton U
 Purdue U
 SNL
 Think Tank, Inc.
 UC Davis
 UC Irvine
 UCLA
 UCSD
 U Colorado
 U Illinois
 U Maryland
 U Rochester
 U Tennessee
 U Tulsa
 U Washington
 U Wisconsin
 X Science LLC


Jon Menard (PPPL)

J. Bialek, J. Canik, J. Chrzanowski, D. Gates, S. Gerhardt, W. Guttenfelder,
 S. Kaye, E. Kolemen, R. Maingi, M. Mardenfeld, D. Mueller, C. Neumeyer,
 M. Ono, E. Perry, S. Raftopoulos, R. Ramakrishnan, R. Raman, Y. Ren,
 S. Sabbagh, V. Soukhanovskii, T. Stevenson, R. Strykowski, P. Titus,
 K. Tresemer, H. Zhang, Y. Zhai, A. Zolfaghari, and the NSTX-U Team

25th Symposium on Fusion Engineering (SOFE)

June 10-14, 2013

The Stanford Court Hotel
 San Francisco, California



Culham Sci Ctr
 York U
 Chubu U
 Fukui U
 Hiroshima U
 Hyogo U
 Kyoto U
 Kyushu U
 Kyushu Tokai U
 NIFS
 Niigata U
 U Tokyo
 JAEA
 Inst for Nucl Res, Kiev
 Ioffe Inst
 TRINITI
 Chonbuk Natl U
 NFRI
 KAIST
 POSTECH
 Seoul Natl U
 ASIPP
 CIEMAT
 FOM Inst DIFFER
 ENEA, Frascati
 CEA, Cadarache
 IPP, Jülich
 IPP, Garching
 ASCR, Czech Rep

Outline

- NSTX-U mission and capabilities
- NSTX results highlights, NSTX-U goals
 - Non-inductive current drive
 - Heat-flux mitigation
- Progress toward completing NSTX-U Project
- Proposed longer-term (5 year plan) enhancements
- Summary

NSTX Upgrade mission elements

- **Advance ST as candidate for Fusion Nuclear Science Facility (FNSF)**

- Motivation for ST as FNSF: high neutron wall loading, potentially smaller size, cost, and tritium consumption, accessible / maintainable


- **Develop solutions for the plasma-material interface challenge**

- Exploit strong heating + smaller R → high P/R and P/S approaching FNSF/Demo levels

- **Explore unique ST parameter regimes to advance predictive capability - for ITER and beyond**

- Fast-ion instabilities and transport
- Electromagnetic turbulence
- High β , rotation, shaping, for transport, MHD


- **Develop ST as fusion energy system**




ST-FNSF




Lithium



“Snowflake”




ITER





ST Pilot Plant


NSTX Upgrade incorporates 2 new capabilities:



- Expect 2x higher T by doubling B_T , I_p , and NBI heating power
 - Reduces v^* → ST-FNSF values to understand ST confinement
- 5x longer pulse-length
 - $q(r,t)$ profile equilibration
 - Test non-inductive ramp-up



- 2x higher CD efficiency from larger tangency radius R_{TAN}
- 100% non-inductive CD with core $q(r)$ profile controllable by:
 - NBI tangency radius
 - Plasma density, position (not shown)





100% non-inductive current drive is essential for steady-state operation of AT/ST next-steps – including FNSF

NSTX achieved:

- Maximum sustained non-inductive fractions of 65% w/NBI at $I_p = 0.7$ MA
- 70-100% non-inductive transiently with HHFW current-drive + bootstrap

NSTX-U projections (TRANSP):


- 100% non-inductive at $I_p = 0.6-1.3$ MA for range of power, density, confinement




$I_p = 1$ MA, $B_T = 1.0$ T, $P_{NBI} = 12.6$ MW

Simulations indicate NSTX-U can test plasma initiation with small or no transformer – required for an ST-based FNSF

- TSC code (2D) successfully simulates CHI $I_p \sim 200\text{kA}$ achieved in NSTX
- TRANSP: NSTX-U more tangential NBI \rightarrow 3-4x higher CD at low I_p (0.4MA)
- TSC: non-inductive ramp-up from 0.4MA to 1MA possible w/ BS + NBI




- TSC + proposed tools support CHI $I_p \rightarrow 400\text{kA}$ in NSTX-U
 - Higher injector flux, B_T , and CHI voltage
 - 1MW 28GHz ECH (increases T_e)





NSTX Upgrade will extend normalized divertor and first-wall heat-loads much closer to FNSF and Demo regimes

Device heat-flux parameters




NSTX-U will test ability of radiation and “snowflake” divertor to mitigate very high heat-fluxes

- NSTX: reduced heat flux 2-4 × via partial detachment (radiation)
- Snowflake → additional x-point near primary x-point
 - Lower B_p → high flux expansion = 40-60 lowers incident q_{\perp}
 - Longer field-line-length promotes temperature drop, detachment



NSTX-U peak heat fluxes will be up to 4-8 × higher than in NSTX






NSTX-U has additional coils for up-down symmetric snowflakes, improved control

Outline

- NSTX-U mission and capabilities
- NSTX results highlights, NSTX-U goals
 - Non-inductive current drive
 - Heat-flux mitigation
- Progress toward completing NSTX-U Project
- Proposed longer-term (5 year plan) enhancements
- Summary

Improved center-stack design to handle increased forces

Identical 36 TF conductors and innovative flex-bus design




See TO2-5 by S. Raftopoulos today at 12:15PM


Center-stack fabrication & assembly proceeding well

Innovative manufacturing techniques developed

Cooling tube soldered with resin-based flux into inner TF conductor



Conductor being wrapped with fiberglass insulation



Insulated conductor being placed into mold



Assembled TF mold ready for Vacuum Pressure Impregnation (VPI) w/ CTD-425



3 of 4 quadrants successfully VPI'd !

Substantial structural and vacuum vessel upgrades

Must handle 4x higher electromagnetic loads

Upper Aluminum Block Internal Reinforcements



Upper Aluminum Block External Reinforcements




Upper Umbrella Arch Reinforcements



Bay-L Cap



TF-Vessel Clevis, TF Outer Leg Support



Relocation of the 2nd NBI beam line box from the TFTR test cell into the NSTX-U test cell completed

TFTR NBI beam box and components successfully tritium decontaminated



Beam Box being lifted over NSTX




Beam Box placed in its final location and aligned



Beam Box being populated with components

Highly tangential 2nd NBI enabled by new port

Outer wall radius moved outward to avoid beam clipping




JK cap


Interior View of Bay J-K



Exterior View of Bay J-K




Aerial View of the NSTX-U Test Cell (May 2013)



Upgrade schedule on track for early finish

Aiming to start research operation in early FY 2015




Critical path through the centerstack fabrication and installation

Forecast Mid October 2014


NSTX-U team is proposing longer-term facility enhancements to fully utilize Upgrade capabilities, support ITER and FNSF

- Improved particle control tools
 - Control deuterium inventory and trigger rapid ELMs to expel impurities
 - Access low v^* , understand role of Li
- Disruption avoidance, mitigation
 - 3D sensors & coils, massive gas injection
- ECH to raise start-up plasma T_e to enable FW+NBI+BS I_p ramp-up
- Begin transition to high-Z PFCs, assess flowing liquid metals



Upward Li evaporator



Divertor cryo-pump





Li granule injector (LGI)




Extended low-f MHD sensor set

Midplane + off-midplane non-axisymmetric control coils (NCC)




1-2MW 28 GHz gyrotron



High-Z tiles



Actively-supplied, capillary-restrained, gas-cooled LM-PFC



Summary: NSTX-U will make leading contributions to fusion science and next-step applications

- **Provide ST basis (and assist AT) for FNSF and for ITER**
 - Actuators + controls for 100% non-inductive at high confinement, β
 - Non-inductive formation and ramp-up - needed for ST, benefits AT
 - RWM control, disruption warning, novel disruption mitigation
 - Non-linear Alfvénic mode dynamics, turbulence at high β and low ν^*
- **Novel plasma-material-interface solutions for next-steps**
 - Lead “snowflake” development, combine with radiation/detachment
 - Lead in liquid metals for recycling/erosion control, vapor-shielding
- **NSTX-U project is on cost and schedule**
 - Project ~65% complete
 - First plasma projected for October 2014

NSTX-U and ST-FNSF presentations

NSTX Accomplishments & Plans

Jon Menard

Oral - Tuesday 11:00

NSTX Upgrade

NSTX Vacuum Vessel Modification

Neway Atnafu

Poster Thursday 2:00-4:00

Power & control system changes

Raki Ramakrishnan

Posters (2) Tuesday 2:00-4:00

Digital Coil Protection System (DCPS) Software

Keith Erickson

Oral - Thursday 12:05

DCPS Overview

Ron Hatcher

Poster Thursday 2:00-4:00

DCPS I/O & Data subsystem

Greg Tchilinguirian

Poster-Thursday 2:00-4:00

Magnet Design & Fabrication

Steve Raftopoulos

Oral - Tuesday 12:15

TF Bundle Failure Cause

Larry Dudek

Poster Tuesday 2:00-4:00

Coolant Tube Solder Technique

Steve Jurczynski

Poster Tuesday 2:00-4:00

Aqua pour coil winding

Mike Mardenfeld

Poster Tuesday 2:00-4:00

Divertor Tile Modif. (CHI gap Protection)

Kelsey Tresemer

Poster- Thursday 2:00-4:00

NSTX Operations

CHI System

Roger Raman

Poster Tuesday 2:00-4:00

Lithium Flash Evaporator

Lane Roquemore

Poster-Thursday 2:00-4:00

NSTX Lithium Pellet Fueling

Daniel Andruczyk

Poster-Thursday 2:00-4:00

ST-FNSF

Poster Tuesday 2:00-4:00

TBR and Shielding - L. A. El-Guebaly

Configuration - T. G. Brown

Mission and Performance - J. Menard

Power and Particle Exhaust - J. Canik

Oral - Thursday 11:35

CS TF Radial Cooling - R. D. Woolley