

# National Spherical Torus eXperiment Upgrade

## Centralized Control System WBS 1.09.04.02

NSTX-U Recovery Project FDR – March 17-19, 2020

---

Ben Smith

Joe Petrella - Cognizant Engineer

Last edit: 3/9/20

# Outline

---

## 1. Overview

## 2. Scope

## 3. Requirements and Interfaces

## 4. Analysis/Prototyping

## 5. Chit Closure

## 6. Procurement, Fabrication, Installation, and Test

## 7. Risk - Project Risks and Design FMECA

## 8. Quality, Environmental, Safety, and Health

## 9. Summary

# Overview - WBS 1.09.04.02

WBS Title	Centralized Control System	WBS #	1.09.04.02
Project Cog.	Joe Petrella	Assoc. Proj. Man.	Tom Jernigan
Design Scope	Replace TFTR-era legacy relay logic with PLC system		
Technical Impact of Scope	CCS will be used to coordinate plant subsystems		
Design Status	FDR completed on 1/14/2020: review <a href="#">link</a> All project chits are closed: <a href="#">link</a> Calculations: N/A Drawings completed: <a href="#">link</a> SoW/Tech Spec: N/A		
Fabrication Status	PLC logic under development at PPPL, COTS parts are selected		
Installation Status	Installation of panels & hardware will begin after CDE-3B approval		

# Outline

---

1. Overview

2. Scope

3. Requirements and Interfaces

4. Analysis/Prototyping

5. Chit Closure

6. Procurement, Fabrication, Installation, and Test

7. Risk - Project Risks and Design FMECA

8. Quality, Environmental, Safety, and Health

9. Summary

# General Functions of the CCS


---

As defined in the RD's, the Centralized Control System shall:

- Receive signals from the PSS-SIS to shut down systems in the event of an E-Stop condition
- Receive feedback and provide enable / arm permissives to:
  - Neutral Beams
  - FCPC Rectifiers & SLD
  - HHFW
  - ECH-PI
- Provide the legacy No E-Stop and Loop Set functions
- Receive status signals from the Trapped Key blocks
- Provide the Chief Operating Engineer (COE) with an HMI to interface with plant systems


# In Scope - Centralized Control System

- Modernize the existing Chief Operating Engineer station
  - Replace 200+ relays with a new PLC & HMI




# Rockwell PLC & HMI Software Solution

- Rockwell L84E PLC & Studio 5000 software
- FactoryTalk View HMI
  - Consistent with adjacent PSS-SIS screens
- Subsystem status feedback & control provided by physical front panel interface
- System provides capability to expand
  - Studio 5000 Logix Emulate creates virtual PLC testing environment
- Data sent via OPC DA to central EPICS NSTX-U archive server
  - Short-term local backup archive using FactoryTalk Data Logging feature



# Scope Includes Panel & Wiring Alterations

- Field wiring changes utilize existing conduits between C-Site and D-Site
- 2 Legacy HIS panels will be replaced as junction boxes
- 1 panel will be modified
- Input signals from PSS-SIS and TKS are accommodated
  - PSS-SIS signals are air-gapped to protect safety system
  - Drive interlock logic for plant subsystems





# Outline

---

1. Overview

2. Scope

3. Requirements and Interfaces

4. Analysis/Prototyping

5. Chit Closure

6. Procurement, Fabrication, Installation, and Test

7. Risk - Project Risks and Design FMECA

8. Quality, Environmental, Safety, and Health


9. Summary

# Requirements Defined and Met


Source	Requirements	Comment	met
<a href="#">NSTX-U-RQMT-GRD-001</a>	Permissives to Subsystems	Operationally sequenced and simple permissives, removed by PSS E-Stop	✓
<a href="#">NSTX-U-RQMT-SRD-012</a>	Defines Interfaces	Specifies which subsystems receive enable/arm signals and which receive simple permissives	✓
<a href="#">NSTX-U-RQMT-SRD-012</a>	Expansion Capacity	System must accommodate future expansion	✓
<a href="#">NSTX-U-RQMT-SRD-012</a>	COE Control Station	HMI will be provided for COE to view & control plant subsystems	✓
<a href="#">NSTX-U-RQMT-RD-025</a>	PSS-SIS and TKS Input Signals	Defines the signals CCS will receive from SIS PLC and TKS key blocks	✓
<a href="#">NSTX-U-RQMT-RD-025</a>	Sequenced Subsystem Signals and Logic	Details the conditions necessary for permissives to be granted and revoked	✓
<a href="#">NSTX-U-RQMT-RD-025</a>	Tag Archive	Data will be transmitted to NSTX EPICS network for central archive	✓
<a href="#">NSTXU_1-7-3-8_RD_101</a>	Software Implementation	Details the features and methods to be implemented in the PLC and HMI programs	✓
<a href="#">NSTXU_1-7-3-8_RD_101</a>	Security	Physical and cyber security defenses	✓

Complete RVTM maintained by Project Systems Engineering

# Interfaces Defined & Accommodated



# Connections Between C-Site & D-Site



Charge question: 2

NSTX-U Recovery Project FDR - (Centralized Control System), March 17-19, 2020

3: Requirements and Interfaces

12

# Details of Interfaces Defined in Interface Control Documents

System 1	System 2	ICD Link	Exposition
Operations & Systems Safety	Heating Systems	<a href="#">link</a>	Defines interface between Centralized Control System and the Heating Systems
Operations & Systems Safety	Power System	<a href="#">link</a>	Defines interface between Centralized Control System and the Power System
Operations & Systems Safety	Vacuum Pumping System	<a href="#">link</a>	Defines interface between Centralized Control System and the Vacuum Pumping System
Operations & Systems Safety	Bakeout System	<a href="#">link</a>	Defines interface between Centralized Control System and the Bakeout System

# Details of Interfaces Defined in Interface Control Documents

System 1	System 2	ICD Link	Exposition
Operations & Systems Safety	Diagnostics	<a href="#">link</a>	Defines interface between Centralized Control System and Diagnostics
Operations & Systems Safety	Cooling System	<a href="#">link</a>	Defines interface between Centralized Control System and the Cooling System

# Drawings Created & Updated via ECN

- Overall 125 existing drawings were reviewed, of those:
  - Voided: 25
  - Redlined: 23
- 31 new drawings created
  - Overview schematic
  - Panel details
  - Control wiring drawings and loop diagrams

ECN/REQUEST#	Drawing	Sheet	Type	Existing / New	Action Required	Ready
ECN 8284	6782E14989	1	Wiring Diagram	Existing	Redline	Y
ECN 8284	6782D14985	1	Interconnection Diagram	Existing	Void	Y
ECN 8284	6782E16220	1	Wiring Diagram	Existing	Redline	Y
ECN 8284	6782D16349	1	Wiring Diagram	Existing	Void	Y
ECN 8284	B-EA3500	60	Wiring Diagram	Existing	Redline	Y
ECN 8284	B-9D1236	1	Wiring Diagram	Existing	Redline	Y
ECN 8284	B-9D1236	2	Wiring Diagram	Existing	Redline	Y
ECN 8284	B-4BA181	1	Wiring Diagram	Existing	Redline	Y

# Outline

---

1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary




# All COTS Items - No Prototyping

---

- All hardware for the project is COTS
  - No custom engineering solutions are employed
- Software components are COTS (Rockwell Automation)
  - In-house expertise with software platform
  - Manufacturer led training at PPPL took place in July 2019
- Soft “prototyping” of the new COE interface
  - Scale printout of the front panel was made
  - Performed test-run of the sequence of plant operations
  - Multiple iterations with COE’s led to current agreed-upon design
- All COE’s are satisfied with the operational control and improved visibility on the status of plant

# Legacy Relay Logic Captured in Diagrams

Logic diagrams created for each plant subsystem, confirmed through discussion with COE's and subsystem supervisors



# Outline

---


1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary

# All Chits have been Closed

8 PDR chits closed by FDR

7 FDR chits closed post-FDR, Design Approval Form completed

APPROVED  
PPPL

 **PPPL** PRINCETON  
PLASMA PHYSICS  
LABORATORY

**ENG-033 - CRR - CHIT RESOLUTION REPORT**  
Centralized Control System FDR Chit Resolution  
Report

*NSTXU\_1-7-3-8\_CRR\_102*

Work Planning #:  
Effective Date: **02/24/2020**  
Prepared By: **Benjamin Smith**

Reviewed By	Benjamin Smith, Preparer	02/20/2020 13:38:38 PM
Reviewed By	Timothy N. Stevenson, Responsible Engineer	02/24/2020 16:23:57 PM
Reviewed By	Yuhu Zhai, Project Engineer	02/24/2020 15:57:56 PM
Approved By	John Dillas, Design Review Chair	02/24/2020 17:04:16 PM

[Link](#)

APPROVED  
PPPL

 **PPPL** PRINCETON  
PLASMA PHYSICS  
LABORATORY

**ENG-033 - CRR - CHIT RESOLUTION REPORT**  
Centralized Control System Chit Resolution  
Report

*NSTXU\_1-7-3-8\_CRR\_101*

Work Planning #:  
Effective Date: **01/09/2020**  
Prepared By: **Benjamin Smith**

Reviewed By	Timothy N. Stevenson, Responsible Engineer	01/07/2020 15:34:45 PM
Reviewed By	Yuhu Zhai, Project Engineer	01/09/2020 09:08:39 AM
Reviewed By	Benjamin Smith, Preparer	01/07/2020 09:57:05 AM
Approved By	John Dillas, Design Review Chair	01/09/2020 13:57:52 PM

[Link](#)

# Outline

---

1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary

# Procurement & Installation

- Components are all COTS, A-3 - detailed in [BOM](#)
- Vendors are identified and pre-qualified
  - Turtle & Hughes 1 Req executed to date, A-1 Qualified
  - Wolock & Lott A-1 Qualified
  - Rumsey A-1 Qualified
- Design support services are integrated into PPPL design team
  - G7 Automation (PLC) BOA in place, 3 req's executed to date
- Construction services are pre-qualified
  - Powers Electric (Conduit & Wiring) BOA in place
  - Maul Electric (Conduit & Wiring) BOA in place
- Installation Procedures per ENG-030 for:
  - Control room cabinet modifications
  - Test cell updates - junction boxes, wiring & conduit

# Testing

---

- Software acceptance testing to validate logical configuration
  - Supported by Studio 5000 Logix Emulate
- Pre-Operational Test Procedures for subsystems
  - Step 1: I/O verification (point-to-point checkout)
  - Step 2: logic testing using override of inputs & outputs
- Cyber security testing to confirm implementation
- Integrated System Test Procedure
  - Full end-to-end system checkout
- Tests will be performed in accordance with ENG-062

# Outline

---

1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary



# Project Risks are Actively Managed

Risk	Score (1-81)	Open/Retired	Risk Retirement Event
No WBS-specific risks for the CCS WBS element			

Generic risks such as component delivery delays are held at the project level in the Risk Registry

# CCS FMECA (I)

System	Failure Mode	Failure Cause	Failure Effect	R	Detection/ Mitigation System (1)	Detection/ Mitigation System (2)	Detection/ Mitigation System (3)	R_R
Central Control System (CCS)	Individual output signal lost	blown fuse	permissive revoke for individual signal, must open cabinet and replace fuse	4	Central Control System (CCS)	None	None	4
Central Control System (CCS)	Individual input signal lost	loose wire or disconnection	loss of status on specific signal, must open cabinet and investigate	4	Central Control System (CCS)	None	None	4
Central Control System (CCS)	HMI loses connection to PLC	HDMI failure	COE loses visibility on one screen, still has front panel and other screens	3	None	None	None	3
Central Control System (CCS)	PLC Input module failure	defective input card	loss of status signals on card	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	PLC Output module failure	defective output card	permissives get revoked from devices on card	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	Controller power supply fails	defective power supply	enter cabinet and replace	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	Fail to enable subsystem	logic error	operations delayed, must connect to PLC and troubleshoot	3	None	None	None	3

# CCS FMECA (II)

System	Failure Mode	Failure Cause	Failure Effect	R	Detection/ Mitigation System (1)	Detection/ Mitigation System (2)	Detection/ Mitigation System (3)	R_R
Central Control System (CCS)	Fail to enable subsystem	I/O wiring error	operations delayed, must investigate cabinet wiring	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	Fail to disable subsystem	logic error	operations delayed, potential to operate subsystem when in unsafe state, must connect to PLC and troubleshoot	3	None	None	None	3
Central Control System (CCS)	Fail to disable subsystem	I/O wiring error	operations delayed, potential to operate subsystem when in unsafe state, must investigate cabinet wiring	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	Fail to disarm subsystem	logic error	potential to operate subsystem in unsafe state, must connect to PLC and troubleshoot	3	None	None	None	3
Central Control System (CCS)	Ethernet connection to network fails	cord failure or disconnected	loss of data archive to EPICS, enable and arm permissives to ECH-PI are revoked	3	Central Control System (CCS)	None	None	3

Charge question: 4

# CCS FMECA (III)

System	Failure Mode	Failure Cause	Failure Effect	R	Detection/ Mitigation System (1)	Detection/ Mitigation System (2)	Detection/ Mitigation System (3)	R_R
Central Control System (CCS)	Key switch input fails	defective key switch module	loss of ability for COE to provide permissive to subsystem, must troubleshoot and replace	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	PSS - CCS input failure	defective input module	loss of signals from PSS, permissives are revoked, must troubleshoot	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	PSS - CCS input failure	loose wire or disconnection	loss of signal from PSS, revoke permissives, must troubleshoot	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	Key switch stuck in active position	defective key switch module	signal remains active until disarm or disable initiated from HMI	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	HMI fault	Defective module	COE cannot control system from HMI, could only be operated through front panel. Subsystems can still be disabled	3	None	None	None	3
Central Control System (CCS)	24V DC power supply failure	Defective module	Must enter cabinet and replace	3	Central Control System (CCS)	None	None	3

# CCS FMECA (IV)

System	Failure Mode	Failure Cause	Failure Effect	R	Detection/ Mitigation System (1)	Detection/ Mitigation System (2)	Detection/ Mitigation System (3)	R_R
Central Control System (CCS)	Network switch failure	Defective module	loss of data archive to EPICS, enable and arm permissives to ECH-PI are revoked	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	PLC network card failure	Defective module	loss of control and loss of EPICS data and/or loss of system control. troubleshoot and replace	3	Central Control System (CCS)	None	None	3
Central Control System (CCS)	loss of power to PLC in control room	breaker trip	permissives and no e-stop signal go to 0V state, subsystems shutdown	2	Central Control System (CCS)	None	None	2
Central Control System (CCS)	Controller stops execution	major fault	loss of control of CCS signals	2	Central Control System (CCS)	None	None	2
Central Control System (CCS)	Fail to disarm subsystem	I/O wiring error	potential to operate subsystem in unsafe state, must investigate cabinet wiring	2	Central Control System (CCS)	None	None	2

# CCS FMECA (IV)

System	Failure Mode	Failure Cause	Failure Effect	R	Detection/ Mitigation System (1)	Detection/ Mitigation System (2)	Detection/ Mitigation System (3)	R_R
Central Control System (CCS)	Individual defeats panel door with uniquely keyed fasteners, touches 120V AC in cabinet		reported incident >50V, low to negligible injury risk	2	None	None	None	2
Central Control System (CCS)	Individual touches 24V DC in cabinet		negligible, <50V	0	None	None	None	0
Central Control System (CCS)	Ethernet port on front panel fails	Disconnected cable	programmer / engineer cannot access PLC without opening panel	0	None	None	None	0
Central Control System (CCS)	USB port on front panel fails	Disconnected cable	programmer / engineer cannot access data archive without opening panel	0	None	None	None	0

27 FMs, all of acceptable risk

CCS provides only permissives, and so does not cause or prevent equipment damage; Can quickly repair COTS components

# Outline

---

1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary

# Software Quality Assurance Addressed


---

- CCS is not responsible for personnel safety: A-3 system
- A-3 systems require no SQA documentation
  - Electing to follow guidelines as best practice
- Software Requirements Document complete
  - Defines system capabilities & implementation constraints
- Software Design Description will be written post-installation
  - Verify implementation of required features from software RD
  - Document control logic & user interface
  - Define how cyber security controls are configured
- Sufficient detail to re-build system
- User documentation - COE operating manual



# Cyber Security Risks Controlled

- Cyber security risks evaluated and classified as moderate risk level system
  - Appropriate controls identified, [test document drafted](#)
- Connection to NSTX-U Controls Network protected by enterprise firewall rules
- Physical panel protected by:
  - Tamper-resistant hardware
  - Door switches
  - COE key locking mechanism



# Safety Concerns Identified

---

- CCS receives air-gapped communication from PSS-SIS
  - No ability to affect the safety-rated system
- Installation will be performed by qualified PPPL staff
  - Appropriate ESHD 5008 (safety manual) sections identified
- Section 2.0: Electrical Safety defines necessary precautions for proposed work & installations (up to 110VAC circuits)
  - Section 2.3: General Requirements
  - Section 2.4: Isolation of Hazards
  - Section 2.7: Electrical Conductors and Connectors
  - Section 2.8: Enclosures for Electrical Equipment
  - Section 2.10: Instrumentation & Control Systems

# Outline

---

1. Overview
2. Scope
3. Requirements and Interfaces
4. Analysis/Prototyping
5. Chit Closure
6. Procurement, Fabrication, Installation, and Test
7. Risk - Project Risks and Design FMECA
8. Quality, Environmental, Safety, and Health
9. Summary

# Summary

---

- CCS meets all defined requirements:
  - Replace existing relay logic with PLC
  - Modernize COE plant interface
  - Provide all existing subsystem signals
- Interfaces are considered in the design and documented in the ICDs and updated drawings
- All chits from design reviews are closed
- No WBS specific risks
- CCS interacts with, but does not compromise the safety functions of, the PSS-SIS